SOUTHVIEW FENCING

PHONE 07825 586807
EMAIL SOUTHVIEW77@HOTMAIL.CO.UK

24.01.2020

Quote

Erect 343meters of stock netting with 2 plain wires on top . 1x set of 12ft half meshed galvanized gates (total gap 24ft) and 1x four foot wooden hand gate cut into rd side hedge near village . All wire tensioned on ratchet strainers, all rails screwed creosote materials .

- 150mm-175mm creosote strainer round posts -2.4m length
- 1.8m creosote 75mm-100mm intermediate posts
- 3.6m 87x38mm rails
- Screws
- 2x galvanized half meshed gates with lockable over clasp
- X4 creosote gate posts
- Labour & VAT
- Tornado r8 80 15 wire
- 4ft tanalised wooden gate

Total price with creosote wooden posts **£3252.78**
Total price with clip ex metal intermediate posts £3224.12